

Fire Station 22 Fiber Optic Infrastructure Extension RFP

Questions/**Answers**

1. What size is the HDPE conduit being placed? **No required size but large enough for a 24-strand fiber cable**
2. Are there any specs for the handholes, pull boxes or term panels? **Handholes should be large enough to contain a service loop and not exceed a minimum bend radius of the fiber**
3. Would there only be one handhole placed on the entire run? Located in front of the new station? **This is optional for the selected vendor. If a new handhole placed by the existing fire station is preferred, then it can be accommodated.**
4. Is there any type of sleeve that needs to be placed under Higgins? **Preferred but not required**